

3-Ton Pkg Heat Pump • 1,200 CFM • Mesa, AZ



1. Flex duct R-8, 0.05 in.wc/100 ft (NCI chart).
2. Sheet-metal drop box ~22×14×12 above Hall 117.
3. Return: 20×30 filter grille in hall ceiling.
4. 4 great-room registers matched 10×10-8.
5. All ceiling registers square – no rectangles.
6. Hall 117 served by door undercuts / transfer.
7. Verify final CFMs with Manual J / Manual D.
8. Pkg unit on roof curb; insulated supply + return drops to attic plenum; balance with dampers.

PROJECT	SYSTEM	SHEET
Mesa, AZ Residence — First Floor Mechanical SCALE: NTS schematic • FLEX sizing per NCI Field Duct Chart @ 0.05 in.wc/100 ft	3-Ton Package Heat Pump (roof) • 1,200 CFM	M1.0 • Duct Layout DRAWN BY: HVAC Design